

## **ADDENDUM #1**

### ACM Tennis Court Renovations Project

**Bids Due: Monday, March 3rd, 2025 at 2:00PM**

#### Questions from the pre-bid meeting & responses:

- 1. Contractor asked if exiting wiring can be used.**  
All new wiring will need pulled from electrical panel
- 2. Specifications and Geotech needed.**  
Added to the ACM website <https://www.allegany.edu/rfp/index.html>
- 3. Information provided states existing fence poles to be reused**  
Due to concern about damage to poles with removal, all new fence poles are required.
- 4. Design states netting sleeve and posts to be reused**  
Due to concern about damage to existing netting sleeve and posts, all new netting sleeve and posts are required.
- 5. Contractors asked for existing foundation design for new lighting posts**  
Contractor is required to design foundation posts and submit stamped shop drawings for approval.
- 6. Most contractors asked about timeline**  
Project can begin anytime after Jun 1, 2025 with preferred project completion prior to September 1, 2025.
- 7. Some of the current fencing is only 4-feet high, but standard height for tennis/handball courts is 10 ft.**  
Current fence height is to be maintained when new fences are installed (some places will be 10 feet and others 4 feet).
- 8. Is there a minority labor requirement?**  
No requirement for minority company ownership or minority labor. However, local Maryland prevailing wages are required.
- 9. Added bid line for Unsuitable Material unit per Cubic Yard**  
Bid would be for the removal of unsuitable material below the sub-base level and to be replaced with suitable fill material or CR-6 Stone

**10. Clarification for bid option #4.**

All areas disturbed outside of final paved areas and gravel trench, shall have a minimum of 4” of top soil placed and seeded & mulched.

**Addendum #1**

Description of the Changes for the plan sheets:

Sheet C-1.0 Cover – Changed Contact Person

Sheet C-2.0 Demo – Note change about reusing fence fabric only, One light Pole was labeled wrong.

Sheet C-3.0 – Site Plan - Adjusted note about New net posts, Added note to OPT #2 about removal of existing trench drains

Sheet C-3.1 Site Plan - Adjusted note about New net posts, Added note to OPT #3 & 4 about removal of existing trench drains

Sheet C-4.0 – E&S Control – No Changes

Sheet C-5.0 Site Details – revised Smart Fence Detail per MDE,

Sheet C-5.1 – can be eliminated, all applicable details are on C-5.0